

Report on Progress of Major Projects

As at 15 May 2016

Project No. & Category	Project Title	Estimated Cost (\$M)	Responsible Bureau / Department	Commencement Date (M/Y)	Completion Date (M/Y)	Project Scope / Remark	Progress / Status
160TB Cat. A	Footbridge Across Po Yap Road Linking Tseung Kwan O Area 55 and Area 65 (MTR Tseung Kwan O Station)	63	Secretary for Development / CEDD	7/2014	7/2016	Works mainly include the construction of a footbridge across Po Yap Road linking Area 55 and Area 65 in Tseung Kwan O.	The construction of footbridge commenced in July 2014. The main bridge was installed in January 2016. Construction of footbridge deck and passenger lift tower is in progress.



Project No. & Category	Project Title	Estimated Cost (\$M)	Responsible Bureau / Department	Commencement Date (M/Y)	Completion Date (M/Y)	Project Scope / Remark	Progress / Status
Head 706 Subhead 6101TX Cat D	Provision of Universal Access Facilities at Public Footbridges, Elevated Walkways and Subways Package 2 – Investigation, Design and Construction	87	Secretary for Transport and Housing / CEDD	4/2015	5/2018	<p>The project aims to provide lift facilities for the following 3 footbridges in Sai Kung District:</p> <ol style="list-style-type: none"> 1. Footbridge across Tong Ming Street near Sheung Tak Shopping Centre (Structure No. NF336); 2. Footbridge across Po Lam Road North near Lam Shing Road (Structure No. NF193); and 3. Footbridge across Po Ning Road near Po Shun Road (Structure No. NF309). 	<p>For NF336, foundation works are in progress.</p> <p>For NF193 and NF309, preparatory works, including application for excavation permits, are in progress.</p>

Project No. & Category	Project Title	Estimated Cost (\$M)	Responsible Bureau / Department	Commencement Date (M/Y)	Completion Date (M/Y)	Project Scope / Remark	Progress / Status
716CL Cat B	Infrastructure Works for Tseung Kwan O Stage I Landfill Site	Under review	Secretary for Development / CEDD	8/2017 (Tentative)	8/2019 (Tentative)	Works comprise the construction of a footbridge (Southern Bridge) across the southern tip of the Eastern Channel, a sewage pumping station in Area 77 and the associated landscaping works.	Detailed design is in progress. The authorization notices for the footbridge scheme and the sewerage scheme were published on 25 September 2015 and 30 April 2015 respectively.

Project No. & Category	Project Title	Estimated Cost (\$M)	Responsible Bureau / Department	Commencement Date (M/Y)	Completion Date (M/Y)	Project Scope / Remark	Progress / Status
822TH Cat. B	Cross Bay Link	Under review	Secretary for Transport and Housing / CEDD	Under review	Under review	<p>Cross Bay Link will be a featured bridge across Junk Bay and will be a landmark of Tseung Kwan O. It will connect Tseung Kwan O – Lam Tin Tunnel to Wan Po Road near Area 86 to cope with the anticipated traffic demand. In addition, it will provide an alternative route to divert traffic away from the Town Centre South so as to improve the living environment of the residential areas in Town Centre South.</p> <p>The Cross Bay Link comprises the construction of an approximately 1.8 km long dual two-lane carriageway with cycle track and footpath.</p>	<p>The associated site investigation works were substantially completed in end 2015.</p> <p>Detailed design is in progress.</p>

Project No. & Category	Project Title	Estimated Cost (\$M)	Responsible Bureau / Department	Commencement Date (M/Y)	Completion Date (M/Y)	Project Scope / Remark	Progress / Status
872TH Cat B	Tseung Kwan O – Lam Tin Tunnel – Main Tunnel and Associated Works	15,093	Secretary for Transport and Housing / CEDD	7/2016 (Provided that funding is secured within this legislative session)	Mid 2021 (Forecast) (Provided that funding is secured within this legislative session)	<p>The main tunnel and associated works of Tseung Kwan O – Lam Tin Tunnel (TKO-LTT) will connect Tseung Kwan O and Lam Tin to meet the transport needs arising from the continuous development of Tseung Kwan O.</p> <p>The main tunnel and associated works comprise a dual two-lane trunk road of approximately 3.8 km long (about 2.2 km in the form of a tunnel) connecting Tseung Kwan O Town Centre in the east to Lam Tin in the west.</p> <p>The works involve reclamation of 3 ha. of land for construction of the depressed Road P2.</p> <p>Slip roads will be provided to connect TKO-LTT with Eastern Harbour Crossing and Cha Kwo Ling Road.</p>	<p>Detailed design has been substantially completed.</p> <p>Tenders for the first 2 works contracts were invited in August 2015 and January 2016 respectively.</p> <p>The Legislative Council Panel on Transport was consulted on the funding application for the project on 23 March 2016. The Panel supported the project.</p>

Project No. & Category	Project Title	Estimated Cost (\$M)	Responsible Bureau / Department	Commencement Date (M/Y)	Completion Date (M/Y)	Project Scope / Remark	Progress / Status
703TH Cat. A	Dualling of Hiram's Highway between Clear Water Bay Road and Marina Cove and Improvement to Local Access to Ho Chung	1,774.4	Secretary for Transport and Housing / TD and HyD	3/2016	End 2020	The project scope mainly comprises widening two sections of Hiram's Highway between Clear Water Bay Road and Ta Ku Ling and between Nam Pin Wai Roundabout and Marina Cove to dual carriageway.	Construction commenced on 30 March 2016.

Project No. & Category	Project Title	Estimated Cost (\$M)	Responsible Bureau / Department	Commencement Date (M/Y)	Completion Date (M/Y)	Project Scope / Remark	Progress / Status
806TH Cat. B	Dualling of Hiram's Highway from Marina Cove to Sai Kung Town	Under review	Secretary for Transport and Housing / TD and HyD	Under review	Under review	The major scope of works comprises improving a section of Hiram's Highway from Marina Cove to Sai Kung Town, Po Tung Road and the section of Tai Mong Tsai Road in the south of Sha Ha. The project aims to cope with the existing and anticipated traffic needs and to alleviate the congested traffic condition.	Sai Kung District Council supported the dual two on-line improvement scheme. During the consultation meetings with key local stakeholders, some stakeholders objected the on-line improvement scheme. Comments received are being reviewed and a public engagement exercise on the project is planned to be held in mid-2016.

Project No. & Category	Project Title	Estimated Cost (\$M)	Responsible Bureau / Department	Commencement Date (M/Y)	Completion Date (M/Y)	Project Scope / Remark	Progress / Status
158TB Cat. B	Elevated Walkway between Tong Ming Street and Tong Tak Street, Tseung Kwan O	221.6	Secretary for Transport and Housing TD HyD	Q4/2016 (Provided that funding is secured within this legislative session)	Mid 2019 (Forecast) (Provided that funding is secured within this legislative session)	Works mainly include the construction of an elevated walkway between Tong Ming Street and Tong Tak Street, and a lift at the end of the walkway near Tong Tak Street.	<p>Detailed design was completed. Funding application for construction works is underway.</p> <p>The Legislative Council Panel on Transport and Public Works Subcommittee discussed and supported the project in the meetings on 23.3.2016 and 20.4.2016 respectively.</p>