

# 背景 Background

交通燈號控制路口按照預設燈號時間操作 Traffic signals operate with predetermined signal time plans





Traffic signals are unable to respond to fluctuations in traffic and pedestrian flows within a short period of time





感應器實時偵測 人流車流狀況

Sensors for real-time detection of traffic and pedestrian flows



系統即時分析並 分配路口燈號時間

Instant analysis and optimisation of traffic signal time

## 實時交通燈號 調節<u>系統</u>

Real-time Adaptive Traffic Signal System



指令輸出至交通燈控制器 以實施交通燈號控制

Instructions to traffic signal controller to control traffic lights



The pilot project and the Tung Chung town centre project are generally operating smoothly.



Optimisation of junction capacity to reduce congestion and unnecessary delay

3

### 實時交通燈號調節系統基本配置

### **Real-time Adaptive Traffic Signal System Basic Configuration**

感應器\*\*

Sensors\*\*

收集實時車龍、車流及人流等數據 Collects real-time traffic queue, traffic flow, pedestrian flow, etc.

### 運算系統\*

#### Computing System\*

分析交通數據,運算合適的燈號時間 Analyses the traffic data and computes the most suitable traffic signal

有線/無線網絡連接

Wired/Wireless Network Connection

現有交通燈控制器 **Existing Traffic** Signal Controller






- 擬議運算系統將裝設於現有交通燈控制器內
- \* Proposed computing system would be installed inside existing traffic signal controller

現有電線 **Existing Cable** 

- \*\* 按個別路口情況選擇合適配置






## 車輛感應器 Vehicle Sensor









行人感應器 Pedestrian Sensor

## 路口特性 Junction Characteristics

不同方向的車流及人流 在短時間內容易出現 較大及不規則的變化 Relatively large fluctuation in traffic and pedestrian flows

路口整體上仍有足夠通行動力, 讓系統有空間可靈活分配綠燈 時間至車流較多的方向


Spare capacity for flexible allocation of green time to approaches with more traffic

個別方向的車流容易因車流量 大幅度變化而出現擠塞情況 Susceptible to congestions due to traffic flow fluctuations

行人過路處的過路按鍵 較常出現被啟動後 但最終沒有行人橫過情況 No pedestrians crossing the road after pressing the pushbutton



## 施工計劃 Implementation Programme



安裝及測試感應器及相關設備
Installation and testing of sensors and associated equipment

系統驗證及調節 System verification and validation 完成測試及開始試行 Completion of testing and trial operation

## Thank you

